



MALWA GRAMIN BANK
HEAD OFFICE, PREM BASTI,
SANGRUR - 148001

Phone 01672- 234642, 500216, 233449, 234643 fax: 01672- 241390

QUOTATION REQUIRED FOR WOOD WORK

Sealed quotations, for interior wood work of our AMH, Fatehgarh Sahib (Sirhind) are invited from the approved contractors of State Bank of India. Site can be visited by the approved contractors during working hours any day. Interior plan and blank quotation of the premises can be obtained from the office of the undersigned or downloaded from Bank's website www.malwagraminbank.com. The last date for receipt of offer in the office of the undersigned is 03.05.2018 up to 2:00 P.M.

General Manager



ਮਾਲਵਾ ਗ੍ਰਾਮੀਣ ਬੈਂਕ

ਮੁੱਖ ਦਫ਼ਤਰ: ਪ੍ਰੇਮ ਬਸਤੀ, ਸੰਗਰੂਰ-148001

ਫੋਨ : 01672- 234642, 500216, 233449, 234643

ਫੈਕਸ :- 01672-241390

ਅੰਦਰੂਨੀ ਵੁਡ ਵਰਕ (ਲੱਕੜ ਦਾ ਅੰਦਰੂਨੀ ਕੰਮ) ਵਾਸਤੇ ਕੋਟੇਸ਼ਨਾਂ ਦੀ ਲੋੜ

ਅਸੀਂ ਆਪਣੇ ਏ. ਐਮ. ਐਚ., ਫੁਤਹਿਗੜ੍ਹ ਸਾਹਿਬ (ਸਰਹਿੰਦ) ਦੀ ਬ੍ਰਾਂਚ ਵਿਚ ਅੰਦਰੂਨੀ ਵੁਡ ਵਰਕ (ਲੱਕੜ ਦਾ ਅੰਦਰੂਨੀ ਕੰਮ) ਵਾਸਤੇ ਕੋਟੇਸ਼ਨਾਂ ਦੀ ਮੰਗ ਕਰਦੇ ਹਾਂ। ਸਾਈਟ ਨੂੰ ਕਦੇ ਵੀ ਕਿਸੇ ਵੀ ਕੰਮ ਕਾਰ ਵਾਲੇ ਦਿਨ ਵਿਜ਼ਿਟ ਕੀਤਾ ਜਾ ਸਕਦਾ ਹੈ

ਕੋਟੇਸ਼ਨਾਂ ਸੀਲ ਕਰਕੇ ਮਿਤੀ 03.05.2018, ਬਾਅਦ ਦੁਪਹਿਰ 2:00 ਵਜੇ ਤੱਕ ਉਕਤ ਪਤੇ ਤੇ ਭੇਜਣ। ਵਧੇਰੇ ਜਾਣਕਾਰੀ, ਅਤੇ ਬਲੈਂਕ (ਖਾਲੀ) ਕੋਟੇਸ਼ਨ ਅਤੇ ਇੰਟੀਰੀਅਰ ਪਲਾਨ ਸਬੰਧੀ ਜਾਣਕਾਰੀ ਸਾਡੀ ਵੈਬਸਾਈਟ www.malwagraminbank.com ਤੋਂ ਡਾਊਨਲੋਡ ਕਰੋ॥

ਮਹਾਂਪ੍ਰਬੰਧਕ

QUOTATION FOR THE INTERIOR WORK OF MALWA GRAMIN BANK, FATEHGARH SAHIB (SIRHIND) BRANCH.

| Sr. No. | Description of Item | Quantity | Unit | Rate | Amount |
|----------------|--|-----------------|----------------|-------------|---------------|
| 1(a) | Low Ht. Partly Glazed Partition | 30.00 | Sq. Ft. | | |
| | Providing & Erection in position low ht. partition 3'-9" high to be made out of 2"x2" partal wood members @ 2'-0" c/c both ways shall ve covered with 6.0 mm thk. Comm. Ply from both sides. The 10mm th. Glass with itching & edge polish shall be fixed above 3'-0" high. The partition to have 2½" x 1/2" steam beach wood member finished with sprit polish on top of the glass etc. Complete as per design. Partitions finished with 1.0mm thk laminate on both sides. | | | | |
| 1(b) | Repair of Low Ht. Partly Glazed Partition | 175.00 | Sq. Ft. | | |
| | Repair of existing Low ht. partly glazed partition change of 6mm ply, laminate. | | | | |
| | | | | | |
| 2(a) | Full Ht. Partly Glazed Partitions | 212.00 | Sq. Ft. | | |
| | Providing & Erecting in position approx. 9'-0" high partitions to be made out 2"x2" partal wood framing @ 2'-0" c/c both ways shall be covered with 6mm thk. Comm. Ply from both sides with proper joinery and anti-termite treatment to wooden frame and plywood. partitions to have 5.0mm thk. Clear glass panels fixed with Steam Beach wood member 1" x 1/2" (above 2'-11" up to 6'-11") with itching as per design and instructions of the architect. The wooden members of partition shall be rigidly fixed to the existing ceiling/floors and the side walls whichever is applicable and as directed. All the exposed grooves shall be finished in polish as per instructions. The necessary openings in partitions shall be provided for A.C. Grills, electrical conduits and other services as per instructions. Partition to have flush door with 4"x2" partal wood frame around with partal wood bracers 2"x 1½" @ 2'-0" center both ways with 6.0 mm thk. Comm. Ply on both sides finished with approved 1.0 mm thk. laminate, handles, dead locks and necessary hardware. complete as per dwg. (ht. of partition up to soffit of false ceiling shall be considered for payment). Partition finished with 1.0 mm thk. approved laminate from both sides. | | | | |
| | | | | | |
| 2(b) | Repair of Full Ht. Partly Glazed Partition | 75.00 | Sq. Ft. | | |
| | Repair of existing Full ht. partly glazed partition change of 6mm ply, laminate. | | | | |
| | | | | | |
| 3(a) | Credenza | 25.00 | Sq. Ft. | | |

| | | | | |
|-------------|--|--------------|----------------|--|
| | Providing and erecting in position credenza for the tables 2'-6" height and 1'-6" deep or as indicated on the drawing to be made out of 19.0 mm thk. Comm. board on all the sides and 6.0 mm thk. comm. ply at the back side with drawer on telescopic sliding channels and openable shutters below the same with one intermediate shelve. The shutters to be made out of 19mm thk. Comm. board with all internal surfaces to be finished in enamel paint, including hinges, ball catch, handles, locks etc. complete as per the direction. The exposed edges shall finished with 5.0 mm thk. steam beach wood leaping duly spirit polish. Credenza shall be finished with 1.0mm thk. approved laminate all sides and top. | | | |
| 3(b) | Repair of Credenza | 17.00 | Sq. Ft. | |
| | Repair of existing Credenza change of 6mm ply, laminate, hardware & enamel Paint inside. | | | |
| 4(a) | Bank Counter | 11.00 | R. Ft. | |
| | Providing and supplying Bank Counter 2'-6" high to be made of 19mm thk. Comm. board finished with 1.0 mm thk. approved laminate. The top of the table shall be finished with 1.0 mm thk. laminate and to have 4" vertical 19.0 mm thk. comm. board laminated member in front of table. The table to have key board drawer on telescopic sliding channels and storage box with one drawer & openable shutter with one intermediate shelf. All internal surfaces to be finished in enamel paint and all exposed edges shall finished with 5.0 mm thk. steam beach wood leaping duly spirit polished. The necessary hardware such as locks, ball catch, handles etc. to be provided, also includes foot rest 2'-0" x 1'-3" x 7" made of 19.0 mm comm. board finished with enamel paint as per the designs and instructions. | | | |
| 4(b) | Repair of Bank Counter | 10.50 | R. Ft. | |
| | Repair of existing Bank counter change of 6mm ply, laminate, hardware & enamel Paint inside. | | | |
| 5 | Cash Counter | 5.00 | R. Ft. | |
| | Repair of existing Cash counter change of 6mm ply, laminate, hardware & enamel Paint inside. | | | |
| 6 | Manager's Table (2'-6" x 6'-0") | 1.00 | Nos. | |
| | Repair of existing Manager's Table change of 6mm ply, laminate, hardware & enamel Paint inside. | | | |
| 7 | Hardware | | | |
| a. | Providing and fixing in position heavy duty double action floor springs ISI marked, to door's including 3mm thick cover plate with screws complete in all respects to architect's approval. | 1.00 | Nos. | |

| | | | | | |
|--|---------------------------|--|--|--------------|--|
| | | | | Total | |
| | *GST AS APPLICABLE | | | | |
| LIST OF APPROVED MANUFACTURES/ PRODUCTS | | | | | |
| S.N. | PRODUCTS | MAUFACTURERS | | | |
| 1 | PLYWOOD 6mm | ISI MARKED | | | |
| 2 | BLOCK BOARD 19mm | ISI MARKED | | | |
| 3 | LAMINATES 1mm | BLOOM, MERINO, SUNMICA, FORMICA | | | |
| 4 | GLASS | MODI-GUARD, SAINT-GOBAIN | | | |
| 5 | LOCKS | GODREJ, HARISON, PALAZA, LINK | | | |
| 6 | DOOR CLOSER/ FLOOR SPRING | ISI MARKED | | | |
| 7 | ADHESIVE | FEVICOL, WOOD-GRIP, JIVANJOUR | | | |
| 8 | PAINT | NEROLAC, ASIAN, ICI | | | |
| 9 | VERTICAL BLINDS | VISTA, MAC, DECK | | | |
| 10 | WOOD | PARTAL, KAIL | | | |
| 11 | TEAK-WOOD | C.P. TEAKWOOD, IVORY COST | | | |



MALWA GRAMIN BANK
HEAD OFFICE, PREM BASTI,
SANGRUR - 148001

Phone: 01672- 234642, 500216, 233449, 234643 Fax: 01672- 241390

QUOTATION REQUIRED FOR WOOD WORK

Sealed quotations, for interior wood work of our Sanghol branch are invited from the approved contractors of State Bank of India. Site can be visited by the approved contractors during working hours any day. Interior plan and blank quotation of the premises can be obtained from the office of the undersigned or downloaded from Bank's website www.malwagraminbank.com. The last date for receipt of offer in the office of the undersigned is 03.05.2018 up to 2:00 P.M.

General Manager



ਮਾਲਵਾ ਗ੍ਰਾਮੀਣ ਬੈਂਕ

ਮੁੱਖ ਦਫ਼ਤਰ: ਪ੍ਰੇਮ ਬਸਤੀ, ਸੰਗਰੂਰ-148001

ਫੋਨ : 01672- 234642, 500216, 233449, 234643 , ਫੈਕਸ :- 01672-241390

ਅੰਦਰੂਨੀ ਵੁਡ ਵਰਕ (ਲੱਕੜ ਦਾ ਅੰਦਰੂਨੀ ਕੰਮ) ਵਾਸਤੇ ਕੋਟੇਸ਼ਨਾਂ ਦੀ ਲੋੜ

ਅਸੀਂ ਆਪਣੀ ਸੰਪੋਲ ਦੀ ਬ੍ਰਾਂਚ ਵਿਚ ਅੰਦਰੂਨੀ ਵੁਡ ਵਰਕ (ਲੱਕੜ ਦਾ ਅੰਦਰੂਨੀ ਕੰਮ) ਵਾਸਤੇ ਕੋਟੇਸ਼ਨਾਂ ਦੀ ਮੰਗ ਕਰਦੇ ਹਾਂ। ਸਾਈਟ ਨੂੰ ਕਦੇ ਵੀ ਕਿਸੇ ਵੀ ਕੰਮ ਕਾਰ ਵਾਲੇ ਦਿਨ ਵਿਜ਼ਿਟ ਕੀਤਾ ਜਾ ਸਕਦਾ ਹੈ

ਕੋਟੇਸ਼ਨਾਂ ਸੀਲ ਕਰਕੇ ਮਿਤੀ 03.05.2018, ਬਾਅਦ ਦੁਪਹਿਰ 2:00 ਵਜੇ ਤੱਕ ਉਕਤ ਪਤੇ ਤੇ ਭੇਜਣ। ਵਧੇਰੇ ਜਾਣਕਾਰੀ, ਅਤੇ ਬਲੈਕ (ਖਾਲੀ) ਕੋਟੇਸ਼ਨ ਅਤੇ ਇੰਟੀਰੀਅਰ ਪਲਾਨ ਸਬੰਧੀ ਜਾਣਕਾਰੀ ਸਾਡੀ ਵੈਬਸਾਈਟ www.malwagraminbank.com ਤੋਂ ਡਾਊਨਲੋਡ ਕਰੋ॥

ਮਹਾਂਪ੍ਰਬੰਧਕ

QUOTATION FOR THE INTERIOR WORK OF MALWA GRAMIN BANK, SANGHOL BRANCH.

| Sr. No. | Description of Item | Quantity | Unit | Rate | Amount |
|----------------|--|-----------------|----------------|-------------|---------------|
| 1 | Low Ht. Partly Glazed Partition | 285.00 | Sq. Ft. | | |
| | Providing & Erection in position low ht. partition 3'-9" high to be made out of 2"x2" partal wood members @ 2'-0" c/c both ways shall ve covered with 6.0 mm thk. Comm. Ply from both sides. The 10mm th. Glass with itching & edge polish shall be fixed above 3'-0" high. The partition to have 2½" x 1/2" steam beach wood member finished with sprit polish on top of the glass etc. Complete as per design. Partitions finished with 1.0mm thk laminate on both sides. | | | | |
| 2(a) | Credenza | 9.00 | Sq. Ft. | | |
| | Providing and erecting in position credenza for the tables 2'-6" height and 1'-6" deep or as indicated on the drawing to be made out of 19.0 mm thk. Comm. board on all the sides and 6.0 mm thk. comm. ply at the back side with drawer on telescopic sliding channels and openable shutters below the same with one intermediate shelve. The shutters to be made out of 19mm thk. Comm. board with all internal surfaces to be finished in enamel paint, including hinges, ball catch, handles, locks etc. complete as per the direction. The exposed edges shall finished with 5.0 mm thk. steam beach wood leaping duly spirit polish. Credenza shall be finished with 1.0mm thk. approved laminate all sides and top. | | | | |
| 2(b) | Repair of Credenza | 7.50 | Sq. Ft. | | |
| | Repair of existing Credenza change of 6mm ply, laminate, hardware & enamel Paint inside. | | | | |
| 3(a) | Bank Counter | 9.00 | R. Ft. | | |

| | | | | | |
|-------------|---|--------------|-------------------|--|--|
| | <p>Providing and supplying Bank Counter 2'-6" high to be made of 19mm thk. Comm. board finished with 1.0 mm thk. approved laminate. The top of the table shall be finished with 1.0 mm thk. laminate and to have 4" vertical 19.0 mm thk. comm. board laminated member in front of table. The table to have key board drawer on telescopic sliding channels and storage box with one drawer & openable shutter with one intermediate shelf. All internal surfaces to be finished in enamel paint and all exposed edges shall finished with 5.0 mm thk. steam beach wood leaping duly spirit polished. The necessary hardware such as locks, ball catch, handles etc. to be provided, also includes foot rest 2'-0" x 1'-3" x 7" made of 19.0 mm comm. board finished with enamel paint as per the designs and instructions.</p> | | | | |
| 3(b) | Repair of Bank Counter | 11.00 | R. Ft. | | |
| | Repair of existing Bank counter change of 6mm ply, laminate, hardware & enamel Paint inside. | | | | |
| 4 | Cash Counter | 5.25 | R. Ft. | | |
| | <p>Providing and erection in position cash counter 2'-6" wide and 3'-9" height to be made out of 19.0 mm thk. Comm. board finished with 1 mm thk. approved laminate. The top of the counter at transaction level 18" wide to have approved color of 20mm. th. granite over 6.0 mm th. comm. ply and at work top 2'-6" wide made out of 19.0 mm comm. board finished with 1.0 mm th. laminate as per design. One keyboard drawer and three drawers including telescopic sliding channels to be provided as per the design and instructions. Each drawer to have multipurpose lock. All exposed edges of board shall be covd. with 5.0 mm thk. Steam beach wood leaping finished with spirit polish and internal surface to be finished with enamel paint. The rates shall includes all hardware items such as knobs, handles, hinges, locks etc. to approval and one intermediate shelf open 12" wide in front along the leg space and 14" wide in the side leg if applicable.</p> | | | | |
| 5 | Manager's Table (2'-6" x 6'-0") | 1.00 | Nos. | | |

| | | | | | |
|--|---|--|----------------|--------------|--|
| | Providing and supplying table for the Chief Manager / Manager 2'-6" high to be made of 19mm thk. Comm. board finished with 1.0 mm thk. approved laminate. The top of the table shall be finished with 1.0 mm thk. laminate and to have 4" vertical 19.0 mm thk. comm. board laminated member in front of table. The table to have key board drawer on telescopic sliding channels and storage box with one drawer & openable shutter with one intermediate shelf. All internal surfaces to be finished in enamel paint and all exposed edges shall finished with 5.0 mm thk. steam beach wood leaping duly spirit polished. The necessary hardware such as locks, ball catch, handles etc. to be provided, also includes foot rest 2'-0" x 1'-3" x 7" made of 19.0 mm comm. board finished with enamel paint as per the designs and instructions. | | | | |
| 6 | Panelling on Main Entrance Door | 40.00 | Sq. Ft. | | |
| | Providing and fixing panelling over main entrance door made out of 2" x 1" partal wood framing @ 2'-0" c/c both ways covered with 6.0 mm thk. Comm. ply. The entire wooden framing and ply is to be given anti-termite treatment. Finished with 1.0 mm thk. approved laminate finish. All exposed edges shall be covered with 5.0 mm thk. Steam beach wood beading. | | | | |
| 7 | Paint on Main Aluminum Glazing & Cleaning of Glass | 250.00 | Sq. Ft. | | |
| 8 | Hardware | | | | |
| a. | P/F Night latches ISI marked Godrej make in cash counter door complete in all respects to bank's approval. | 1.00 | Nos. | | |
| b. | Providing and fixing in position heavy duty double action floor springs ISI marked, to door's including 3mm thick cover plate with screws complete in all respects to architect's approval. | 1.00 | Nos. | | |
| c. | Providing and fixing in position Voucher Stand. | 1.00 | Nos. | | |
| d. | Providing and fixing in position Clearing Box. | 1.00 | Nos. | | |
| e. | Providing and fixing in position Suggestion Box. | 1.00 | Nos. | | |
| | | | | Total | |
| | *GST AS APPLICABLE | | | | |
| LIST OF APPROVED MANUFACTURES/ PRODUCTS | | | | | |
| S.No. | PRODUCTS | MAUFACTURERS | | | |
| 1 | PLYWOOD 6mm | ISI MARKED | | | |
| 2 | BLOCK BOARD 19mm | ISI MARKED | | | |
| 3 | LAMINATES 1mm | BLOOM, MERINO, SUNMICA, FORMICA | | | |
| 4 | GLASS | MODI-GUARD, SAINT-GOBAIN | | | |
| 5 | LOCKS | GODREJ, HARISON, PALAZA, LINK | | | |

| | | |
|-----------|---------------------------|--------------------------------------|
| 6 | DOOR CLOSER/ FLOOR SPRING | ISI MARKED |
| 7 | ADHESIVE | FEVICOL, WOOD-GRIP, JIVANJOUR |
| 8 | PAINT | NEROLAC, ASIAN, ICI |
| 9 | VERTICAL BLINDS | VISTA, MAC, DECK |
| 10 | WOOD | PARTAL, KAIL |
| 11 | TEAK-WOOD | C.P. TEAKWOOD, IVORY COST |

